

Quotation

Date: - 12-05-25

Attention: Mr. Shyju Parayil

Ref: ET-QTN25-2891-00

Hindu Temple Dubai, Jebel Ali Village, Dubai

Mob: +971545842950, Email: it@hindutempledubai.com, mohan@hindutempledubai.com

Subject: Quotation for Aluminum Gate Work @ JAV Hindu Temple, Dubai.

Dear Sir,

Thank you for your enquiry and providing opportunity to quote you on the above Job. Below is our best quote for your perusal. Hope this will be in line with your requirement with consideration of our quality services and timely work completion.

Our Estimated Price

Our best quote with our quality services for this Work is as below, hope this is in line with your requirement.

Sl. #	Location	Task	Scope of work	Unit	Qty	Unit Rate	Total Cost	Remark
1.	GF Outdoor	Aluminium gate work	Fabrication, supply & installation of Aluminum white powder coated heavy duty sliding gate @ JAV Hindu Temple as per attached annex-01-00.	Lot	1	19028.90	19028.90	
Total							19028.90	
Vat 5%							951.45	
Grand Total							19980.35	

Disclaimer: - Works mentioned/quoted above are only limited to the provided photos/locations pertaining to photos within appendix A / site visit discussions. Any additions will be quoted separately as if to be done. For tiles/cladding/paint project approved products/RAL/Manufacturer/local supplier/technical details to be provided by client or similar products will be used. EITS will not hold responsible for any slight differences due to usage of similar products (in absence of information from client end).

Bank Details:

A/C Name: Eco Innovative Technical Services LLC

SWIFT Code: UMMQAEAD

Bank Name: National Bank of Um Al Quwain (NBQ)

Account No: '0086310167

Bank Address: Main branch, Khalid Bin Al Walid Street, Dubai

IBN: AE340420000000086310167

Scope of work- M/s EITS LLC

Sl #	Work Description	SOW Relevant remarks
1.	Fabrication, supply & installation of Aluminum white powder coated heavy duty sliding gate partial blocked view, all aluminum joints welded. @ JAV Hindu Temple as per attached annex-01-00.	Any existing damage / electrical, mechanical part failure found during work will be notified & subject to additional cost as/if applicable.

Scope of work Client

1. Access permit / Pass, any design related approval if applicable.
2. Welfare facilities for workforce. Utilities like power supply, light and water etc....
3. Equipment, power shutdown and restart shall be in client supervision and under his responsibility if applicable.

Terms & Conditions

Payment Terms:

- All invoices are subject to **5% VAT**.
- 50% advance rest CDC immediate after work completion.

General Terms:

- Delivery within 3-4 weeks from the date of order confirmation with signed LPO.
- Work completion 3-4 working days from date of access & material availability.

Validity:

- Validity 7 Day from the date of Offer.

Should there be a need for further clarification, please do communicate to us. It would be our privilege to assist you.

Thanking you,

For Eco Innovative Technical Services LLC



S P Singh M D [Mob: 0501768742](tel:0501768742)

**EITS SCOPE OF WORK (SOW)**

Date: 12-May-25

Annex: 01-00

Project: Aluminum gate work @ JAV Hindu Temple

Quote Ref: ET-QTN25-2891-00

Sl. #	Location	Task	Scope of work	Qty	Unit	Unit Rate	Total Cost	Remarks
1	GF Outdoor	Sliding Gate	Fabrication, supply & installation of Aluminium white powder coated heavy duty sliding gate partial blocked view, all aluminum joints welded, sanded & buffed Size 5200 x 2400 mm as per below details.	1	Lot	16806.90	16806.90	
1.1	GF Outdoor	Sliding Gate	Aluminium Fix Panel Size 1050x1500mm	1	Lot			
1.2	GF Outdoor	Outer frame	Gate outer frame made with Aluminum profile 120x50x3 mm	1	Lot			
1.3	GF Outdoor	Verticle Tubes	Different type of aluminum vertical tubes. 80x20 mm, 40x20 mm, 120x20 mm on 40 mm gap. Backed with aluminum sheet partial blocked view.	1	Lot			
1.4	GF Outdoor	Bottom rail	Steel flat bar 75x8 mm double length of gate length. Wheel with ball bearing SS hevy duty 4 nos.. Guide roller & wheels at top 8 nos.	1	Lot			
2	GF Outdoor	Aluminu m fix panel	Fabrication, supply & installation of aluminium Fix Panel partial blocked view, all aluminum joints welded, sanded & buffedSize 1050x1500 mm using same material as above.	1	Lot	1815.00	1815.00	
3	GF Outdoor	Transpor tation	Transportation charge	1	Lot	407.00	407.00	
Sub Total							19028.90	
Vat 5%							951.45	
Grand Total							19980.35	

Disclaimer:- Works mentioned/quoted above are only limited to the provided photos/locations pertaining to photos within appendix A / site visit discussions. Any additions will be quoted separately as if to be done. For tiles/cladding/paint project approved products/RAL/Manufacturer/local supplier/technical details to be provided by client or similar products will be used. EITS will not held responsible for any slight differences due to usage of similar products (in absence of information from client end).

Bank Details:

A/C Name : Eco Innovative Technical Services LLC

SWIFT Code: UMMQAEAD

Bank Name : National Bank of Um Al Quwain (NBQ)

Account No: '0086310167

Bank Address: Main branch, Khalid Bin Al Walid Street, Dubai

IBN : AE340420000000086310167